COUNTY OF ERIE

MARK C. POLONCARZ
COUNTY EXECUTIVE
DEPARTMENT OF ENVIRONMENT & PLANNING

THOMAS R. HERSEY, JR.
COMMISSIONER

JOSEPH L. FIEGL, P.E.
DEPUTY COMMISSIONER

October 23, 2017

Mr. Terry Enderton
Visone Construction, Inc.
79 Sheldon Ave.
Depew, NY 14043

RE: Sewer Repair Term.Contract
Contract No. 79
Work Order No. 1
ECSD No. 3

Dear Mr. Enderton:

Please consider this the formal issuing of **Work Order No. 1** for the Sewer Repair Term Construction Contract No. 79. This Work Order consists of a repair on Oliver Place in the Village of Hamburg and Erie County Sewer Districts No. 3.

The repair area is located at the downstream/west invert of Manhole CE1AC at the intersection of Oliver Place and Buffalo Street in the Village of Hamburg. The existing sewer mainline is 12-inch diameter; however, a 10-inch diameter sewer repair extends approximately three (3) linear feet out of the manhole. The work shall consist of replacement of the 10-inch diameter pipe with new 12-inch diameter sewer, coring a 12-inch new manhole connection, manhole benchwork, and associated restoration activities. Please refer to the attached map and an Engineer's Estimate of the anticipated quantities. The Estimate for this work is $6,186.00; however, the final cost shall be determined based on field quantities verified by the Inspector. It is noted that the minimum length of repair paid shall be 10 linear feet.

Per the Contract Documents, please begin work within five (5) business days. Please provide me with a proposed work schedule, homeowner notification procedure, bypass pumping and traffic control plans, and any other submittals or permits as required per the contract, prior to mobilizing under this Work Order.

Please be mindful that the MBE and WBE utilization goals for this contract are 10% and 2% respectively, and the apprenticeship training program goal is 10% of the workforce.

If you have any questions please contact me at 716-858-6145.

Sincerely,

Nadine Wetzel

Nadine R. Wetzel, P.E.
Sanitary Engineer

CC: ECSD No. 1, 2, 3, 4, 5, 6, 8 BOM
J. Fiegl/G. Pecak/W. Lardo/J. Russell/J. Desjardins/0.3.3.79 (w/enc)
S. Canestrari/R. Rehac (w/enc)
R. Ferber

Item 6(c)(i)