October 30, 2015

Thomas & Carol McFaul
4195 Robin Ln
Hamburg, NY 14075

RE: Erie County Sewer District Nos. 1, 2, 3, 4, 5, 6, 8
Sanitary Sewer Manhole Rehabilitation and Replacement Project
Contract 74
Construction Activity Notice

Dear Property Owner/Resident:

The Erie County Department of Environment & Planning, Division of Sewerage Management is beginning a sanitary sewer manhole rehabilitation initiative to repair deteriorating manholes throughout the County. This letter is to inform you that a manhole on or near your property is scheduled for either rehabilitation or replacement under the current Sanitary Sewer Manhole Rehabilitation and Project, Contract 74.

The rehabilitation method to be used on the majority of the manholes is commonly referred to as Spin Lining and involves the use of an air compressor to spin a nozzle to which a wet cementitious material is fed. This results in a complete and even coating of the interior of the manhole to seal and reinforce the existing structure once cured. The process should take no longer than one (1) day and should cause minimum interruption. The contractor is responsible for any necessary restoration to your lawn or property resulting from their activities. The contractor will inform you in advance if any temporary fence opening or tree removal will be required to complete rehabilitation work. In a limited number of cases a full manhole replacement will be required which will result in the need for larger equipment to excavate, remove, and replace the existing manhole. In these cases you will also be notified in advance of any excavation.

Please call the person at the number listed below if you have any particular questions and /or concerns regarding the project.

- **Erie County Project Manager - Garry S. Pecak, P.E.** – 858-6267
- **Erie County Assistant Project Manager – Dan Skowronski** –858-6472
- **Contractor – Kandey Company, Inc. – Richard Szucs Jr,**– 675-7245
- **Construction Inspector – Daniel Car** – 445-9672
- **Emergencies** – In case the above-mentioned individuals cannot be reached, please contact the Erie County Sewer District No. 3 Operations Office at 823-8188.

Item 6(b)(iii)

Thank you for your consideration in this matter.

Very truly yours,

Garry S. Pecak, P.E.
Sanitary Engineer

GSP:bp

Cc: Board of Managers, ECSD Nos. 1,2,3,4,5,6,8
Richard Szucs Jr, Kandey Company Inc.
J. Carr/B.Lardo/D. Skowronski/0.3.3.74 (w/address list)
S. Canestrari, ECSD Nos. 3,6,8 (w/address list)
R. Rehac, ECSD Nos. 1,4,5 (w/address list)
B. Strzeszynski, ECSD No. 2 (w/address list)
G. Absolom/ K. Kaminski
V:\Sewerage Management\Project Files\Construction\0\74\ResidentLtr-MHrehab.docx